HASSAN DIVISION.

Abstract Notification dated 3rd—4th August 1927.

Reference is invited to the advertisement published in detail in the *Mysore Gazette* dated 11th August 1927 advertising the date of submission of tenders for restoring Yogihally tank in Hassan taluk.

N. G. KRISHNA IYENGAR,
Executive Engineer.

KADUR DIVISION.

Dated 4th August 1927.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 1st September 1927, for Constructing a new out-Patient Dispensary for the Maternity Hospital at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chcikmagalur between the hours of 2 to 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees Two Hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a New out-Patient Dispensary for the Maternity Hospital at Chikmagalur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for Constructing a New out-Patient Dispensary at Chikmagalur, Kadur Division.

Sl. No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in	C.yd.	138
2	Concrete in lime mortar	C.ft.	1,613
3	Burnt stone in chunam	„	2,732
4	Burnt brick in chunam	„	5,465
5	Burnt stone slabs of 4½" dressed and set in mortar ..	S.ft.	290
6	Burnt brick in chunam (Arch work)	C.ft.	259
7	Circular pillars of lime concrete and forming base and cap as per design	R.ft.	51
8	Chunam plastering two coats	Sqr.	102·36
9	White and colour washing	„	102·36
10	Cement pointing to basement	„	5·85
11	Teakwood trusses 1" dia. tie rod, struts 3" × 3" as per design complete	No.	3
12	Teakwood wrought and put up with oiling	C.ft.	278·31
13	Roofing 1st class Mangalore Tiles on teak rafters, nails etc.	Sqr.	19·58